

BOSTON PUBLIC LIBRARY



3 9999 06583 552 0

GOVDOC

BRA

3388

No. 4

X-100-1-9.
BOSTON REDEVELOPMENT AUTHORITY

FEASIBILITY STUDY

REPORT NO. 4

BOSTON PUBLIC LIBRARY

File



W. CHESTER BROWNE AND ASSOCIATES, INC.
ARCHITECTS AND ENGINEERS
122-128 Arlington Street, Boston, Massachusetts

PRELIMINARY DRAFT
FEASIBILITY STUDY
FOR
PROTOTYPE PLANS
FOR A
MULTI-STORY LIGHT MANUFACTURING PLANT
IN THE
SOUTH END URBAN RENOVATION AREA
IN THE CITY OF BOSTON

REPORT NO. 4

September, 1963

Prepared for
BOSTON REDEVELOPMENT AUTHORITY
BOSTON, MASSACHUSETTS




Aug. 17, 1926

D25

B

V.4



REPORT NO. 4

Physical features of the prototype have been described, and architectural design drawings submitted in previous reports. This report contains further detail, outline specifications, material take-off, preliminary engineering cost estimate and cost analysis.

In order to properly determine the most suitable and economical framing scheme for the building, we have made an analysis of various applicable structural systems.

Drawing S-1 shows framing and cost analyses for a typical bay for six different structural systems considered worth investigation. For comparison, we have included the two systems considered most suitable for the prototype in our preliminary engineering cost estimate section of this report. They are designated on Drawing S-1 as Scheme #1, Concrete Flat Slab with Drop Panels and Scheme #4, Two Way Grid Flat Slab. Total cost estimates for reinforcement, concrete and formwork are given in the column at the right-hand side of the drawing. Scheme #4 is \$1.81 per square foot. Scheme #1 is \$2.03 per square foot. The volume of concrete for the column and its capital is the same for both systems. The volume of concrete in the grid flat slab for a typical bay is 20 cubic yards, and for the flat slab with drop panels is 23 cubic yards. The saving in concrete for the grid flat slab will also be reflected as a saving in foundation cost, due to the reduction of dead load. This is delineated on Drawing A-11 which shows the estimated number of piles required at each column location for the above two systems and for a 4 and 6 story building. Due to the magnitude of the column loads and the nature of the soil in the area, we have based our foundation analyses on the use of concrete filled steel shell piles driven to refusal, with a load capacity of 105 tons per pile.

Digitized by the Internet Archive
in 2011 with funding from
Boston Public Library

We believe the average length of the piles will be 60 feet at an estimated cost of \$10.00 per lineal foot or \$800.00 per pile.

Pages 1 to 10 inclusive of the preliminary engineering cost estimate section contain cost breakdowns of various parts of the work.

Pages 11 through 14 inclusive are cost summaries of 4 and 6 story buildings for both flat slab with drop panels and grid flat slab construction.

Page 15 is a tabulated cost analysis for the " buildings. It gives the total cost for each building and the proportion of total cost attributable to the various parts of the work.

The difference in cost between the flat slab and the grid flat slab systems for a 4 or 6 story building, respectively, is relatively small in the overall picture, but it is sufficient to recommend the use of the grid flat slab. The 6 story height is the most economical to build in terms of dollars per square foot building cost.

The cost analysis shows that buildings of this size and construction may be built for about \$13.00 per square foot.

Additional stories beyond 6 will reflect an increase in cost per square foot because vertical transportation facilities would have to be increased to properly serve the added building population and area.

Additional horizontal increments in depth of the building will also increase the cost per square foot for the same reason.

Additional horizontal increments in length of the building will produce the same result, magnified by the cost of incorporating an expansion joint through the building.

OUTLINE SPECIFICATIONS

for a
MULTI-STORY PROTOTYPE LIGHT MANUFACTURING PLANT
in the
SOUTH END URBAN REDEVELOPMENT AREA
in the
CITY OF BOSTON

Prepared for
BOSTON REDEVELOPMENT AUTHORITY
BOSTON, MASSACHUSETTS

• • • • •

W. CHESTER BROWN AND ASSOCIATES, INC.

ARCHITECTS AND ENGINEERS
122-128 Arlington Street
Boston, Massachusetts

CONSULTING ENGINEERS INCORPORATED

122-128 Arlington Street
Boston, Massachusetts

REPORT NO. 4

September, 1963

Project No. 73962

OUTLINE SPECIFICATIONS, MULTI-STORY PROTOTYPE LIGHT MANUFACTURING PLANT,
SOUTH END URBAN RENEWAL AREA, CITY OF BOSTON, BOSTON PUBLIC WORKS DEPARTMENT

TABLE OF CONTENTS

<u>SECTION NO.</u>	<u>DESCRIPTION</u>	<u>PAGE NO.</u>
I	ARCHITECTURAL	2 to 3 inclusive
II	PLUMBING	9 to 12 inclusive
III	HEATING AND VENTILATING	13 to 16 inclusive
IV	ELECTRIC WORK	17 to 24 inclusive

OUTLINE SPECIFICATIONS

SECTION I

ARCHITECTURAL

-1. SCOPE OF THE PROJECT. -

The project consists of a multi-story manufacturing plant to be erected in the South End Urban Renewal Area located within the City of Boston.

The building will be 4 or 6 stories in height, and will have a partial basement. There will be a crawl space under the remainder of the building area with access from the basement. The basement will contain a Boiler Room, Transformer Vault, Electric Service Room, Milling Maintenance, Storage, and Custodians' Room.

Each typical floor will have 4 tenant spaces consisting of Office and Manufacturing areas, toilet facilities, and stairways.

Freight elevator service is provided for each part of tenant areas.

The building is served by two passenger elevators. Elevator machines are located in Penthouses on the roof.

The building is 6 bays long and 4 bays wide, all bays 28' x 28'. A continuous loading platform with canopy extends the full length of the rear of the building, at the ground floor level.

-2. PREPARATION OF SITE. -

This includes removal of all existing obstructions, all excavation and backfill, fill placement and compaction, installation of bituminous concrete roads and parking areas, concrete walks, seeding and all related items to fully complete the work within the project limits.



OUTLINE SPECIFICATIONS - SECTION I - ARCHITECTURAL (cont.)

I-3. FOUNDATIONS. -

The building is to be entirely supported on concrete filled steel shell piles, driven to refusal. Each pile to have a load capacity of 125 tons. Pile caps, grade beams, basement walls and floors are to be reinforced concrete.

I-4. FRAMING. -

The superstructure will be of reinforced concrete columns, grid flat slab floor and roof slabs with no drop panels, reinforced concrete beams at stair, elevator and shaft openings three floors, and reinforced concrete spandrels.

I-5. MASONRY. -

Except for the insulated panels at the window facades, exterior walls of the superstructure are face brick, solid to concrete masonry back-up units. Where back-up is the reinforced concrete frame, Corbello tiles and galvanized steel anchors will be used.

Limestone will be used for window sills throughout and for trim on the office facade.

Permanent interior partitions will be concrete masonry units.

Entrance stairs in main lobby are reinforced concrete with pre-cast terrazzo treads and risers.

Concrete floors in manufacturing areas, basement and loading platform will be left exposed and receive a floor hardener treatment.

I-6. ROOFING AND FLASHING. -

In general, roofing will be 20 year, bonded built up roofing, applied over rigid insulation and vapor barrier. Base flashings will be built up, cap flashings will be copper.

OUTLINE SPECIFICATIONS - SECTION I - ARCHITECTURAL (continued)

Roofs will have standard roof drains and interior downpipes. Through wall flashing at exterior wall openings to be 5 ounce protected paper.

I-7. METAL WINDOWS. -

All windows will be intermediate grade, projected, steel, prepared to receive screens, ventilators as shown. Windows to be primed and bonderized, delivered with one shop coat of paint and be complete with hardware.

I-8. METAL CURTAINWALL. -

Curtainwalls to be 12 gauge, formed horizontal and vertical frames, welded construction, factory assembled. Panels approximately 3-3/4" thick, 18 gauge, galvanized, bonderized steel pan type with fibreglass insulation, and faced on the outside with 16 gauge porcelain enameled sheet with joints sealed edges, "U" factor not more than .12. Grid units and backing will be delivered with one shop coat of paint.

I-9. DAMP-PROOFING, WATER-PROOFING, CAULKING. -

Unless otherwise noted, all basement walls will be damp-proofed with two coats of brush applied bituminous material on the exterior face up to finished grades.

All exterior openings in masonry walls to be perimeter caulked with plastic caulking compound.

Waterproofing to be installed where required to be metallic cement plaster type.

I-10. GLASS AND GLAZING. -

Glass for metal sash to be double strength "B" quality, set in glazing compound.



OUTLINE SPECIFICATIONS - SECTION I - ARCHITECTURAL (continued)

Aluminum entrances will be narrow style with 1/4 inch plate glass.

E-11. MISCELLANEOUS IRON. -

This includes steel stairs, railings, elevator beams, metal thresholds, and guard angles.

Typical interior stairs will be pen type with 1/2 inch treads and landings and standard steel pipe rails. Stairs and entrance lobby will have aluminum rails.

E-12. METAL DOORS AND FRAMES. -

Interior doors in permanent partitions will be 16 gauge, 1-3/4 inch thick hollow metal with 16 gauge pressed metal on interior face, jamb and trim.

E-13. METAL LATH AND PLASTER. -

Ceilings in toilet areas will be suspended with channel, metal lath and three coat plaster, finish coat (hard smooth).

E-14. ACOUSTICAL TILE. -

Ceilings in the office areas and main corridor will be removable 2' x 4' acoustical panels, 1" thick. Exposed face of panels to be perforated .01" thick steel, back panel to be solid of same thickness, edges to be mechanically locked. Sound absorbing element to be non-dusting fibrous glass. Finish to be baked white enamel. Panels to be supported on an exposed T grid system with same enamel finish, and shall provide complete access to the space above the ceiling.

Acoustical ceilings are to be co-ordinated with lighting systems.

OUTLINE SPECIFICATIONS - SECTION I - ARCHITECTURAL (continued)

I-15. HARDWARE. -

All hardware shall be supplied and installed to adequately equip all operating units.

Keying system will be a Grand Master Key System.

I-16. TILE.-

Toilet rooms and service closets will have ceramic, non-slip tile floors and glazed ceramic tile dado. Dados will be applied by the thin set mortar method.

I-17. TERRAZZO. -

Main entrance vestibule and lobby will have terrazzo floor and base. Main entrance stairs will have pre-cast terrazzo treads and risers.

I-18. RESILIENT FLOORING. -

Corridors and office areas will have 1/8" thick 12" x 9" asphalt tile floor covering. Masonry partitions adjacent to asphalt tile floors will have 4" high, standard rubber, set-on type base.

I-19. TOILET COMPARTMENT PARTITIONS. -

Toilet compartment partitions will be floor supported, flush type enameled steel partitions and doors.

I-20. MOVABLE OFFICE PARTITIONS. -

To be stock, flush type steel, sound deadened, movable units, heights as noted, factory finished, in baked enamel, designed to quickly accommodate any change in layout after original installation. All partitions and parts to be 100% reusable. All units to be shipped from the factory in one piece, all panel and door units interchangeable.



OUTLINE SPECIFICATIONS - SECTION I - ARCHITECTURAL (continued)

Doors to be 1-3/4" thick, complete with hardware. Doors shall be removable both sides for ready access to wiring raceway.

I-21. MOVABLE WIRE MESH PARTITIONS, MANUFACTURING AREA, -

To be stock, interchangeable, prefabricated, movable standard units which can be arranged in any desired combinations, heights as noted, fabricated of 10 gauge steel wire woven into 1-1/2" diamond mesh securely welded to cold rolled channel frames. Door and service windows per plan shown, all factory finished in baked enamel, and complete with hardware. All partitions and parts to be 100% reusable.

I-22. OVERHEAD DOORS, -

Doors from manufacturing areas to freight elevators vestibules are roll-up interlocking steel slab, chain operated.

Overhead doors to loading platform are heavy duty steel, sectional type with counterbalance torsion spring. They shall be placed as indicated.

I-23. ELEVATORS, -

Each passenger elevator will be 2000 pound, 12 person capacity with speed of 200 feet per minute, 6'-4" wide x 4'-5" deep platform size, automatic leveling, push button duplex selective operation, with horizontally sliding doors. Elevator machines located directly over the hoistway in a penthouse.

Each freight elevator will be 3000 pound capacity, Class C industrial truck loading, speed of 75 feet per minute, 10'-0" x 10'-0" platform, automatic leveling, with manually operated bi-parting vertical sliding doors. Machines to be located directly over the shaftway in a penthouse.



OUTLINE SPECIFICATIONS - SECTION I - ARCHITECTURAL (continued)

I-24. PAINING. -

This includes the painting of all interior concrete masonry partitions, exposed interior surfaces of exterior concrete masonry walls, interior exposed concrete surfaces except floors, interior plaster ceilings, exterior and interior ferrous metal, except factory finished movable partitions.

OUTLINE SPECIFICATIONS

SECTION II

PLUMBING

II-1 SCOPE. -

- (a) Sanitary Drainage System:- Complete sanitary drainage system within the building, connecting to all fixtures, equipment, drains and vertical runs with tap-offs in shafts throughout the building for tenant use, extending and terminating the building main drains at a point ten feet outside the building.
- (b) Storm Drainage System:- Complete storm drainage system in building for interior roof drains and canopy drains, extending and terminating the building main drains at points 10 feet outside the building.
- (c) Domestic Cold Water System:- Complete domestic cold water system within the building, connecting to all fixtures, equipment, and vertical runs with valved tap-offs in shafts provided for tenant use. The system shall begin ten feet outside the building having a meter just inside and run horizontally in the basement area and crawl spaces rising where necessary.
- (d) Domestic Hot Water System:- Complete domestic hot water system within the building; connecting to all fixtures, equipment, vertical risers with valved tap-offs in shafts provided and including steam run 140°F. hot water storage heaters in boiler room area. System shall include recirculating main with circulating pump. Mains shall be run through basement and crawl space areas.
- (e) Gas System:- Complete gas piping system inside the building from the meter provided by the Boston Gas Company. The interior system shall include low pressure gas mains and risers, including risers with valved tap-offs in utility shafts.



OUTLINE SPECIFICATIONS - SECTION II - PLUMBING (continued)

All branches to gas firing equipment and appliances will be valved.

(f) Sprinkler System:- A complete sprinkler system will be installed in the basement and boiler room areas only and shall be installed in accordance to the latest City of Boston Code and the National Fire Protection Association. Fire extinguishers will be installed throughout the building to NBFU standards.

II-2. INSTALLATION:-

Installation shall be in accordance with the latest applicable City of Boston and Commonwealth of Massachusetts Codes.

II-3. MATERIALS. -

(a) Underground water services and exterior piping above 4" size - cast iron cement lined bell and spigot class 150 water pipe with Class "D" cement lined fittings; joints to be made with calum and lead.

(b) Interior water piping 4" and under - all hot, cold, recirculating water inside the building shall be type "L" copper tubing with cast brass fittings suitable for soldered joints. Joints shall be made with 95-5% tin-antimony solder.

(c) Gas Service - Standard weight iron size black steel pipe with screwed and/or welded joints.

(d) Soil, waste, vent and roof conductor piping. Extra heavy cast iron bell and spigot soil pipe and fittings. Joints made with calum and lead. Vent piping 2" and smaller installed above ground may be galvanized standard weight steel pipe with cast iron fittings. Short waste branches to fixtures may be type "L" copper tubing or iron size brass or copper pipe with recessed drainage fittings.

OUTLINE SPECIFICATIONS - SECTION II - PLUMBING (continued)

(e) Sprinkler piping - Standard weight black iron steel pipe with malleable iron screwed fittings.

(f) Insulation - Pipe insulation shall be 1-1/2 inch molded fibrous glass low pressure insulation. Cold water and roof conductor lines shall have vapor barrier. Exposed piping shall have an additional 3 ounce canvas jacket. Hot water tanks shall be insulated with 1-1/2 inch thick 85% magnesia blocks with hard cement coat finish.

(g) Hot water storage heaters - Hot water storage tanks shall be constructed of steel with copper lining built for 117-1/2 pounds working pressure in accordance with ASME and Massachusetts standard requirements. Tank shall be heated by steam with copper heating coils located inside the tank.

(h) Hot water circulating pump shall be automatic electric motor driven all bronze body of capacity required.

(i) Valves - Valves on water lines to be bronze or brass throughout with packing glands, stuffing boxes and nuts, solid wedge, screw or union bonnets, designed for 150 pound steam working pressure and shall have screwed ends except for sizes above 3 inches.

(j) Cleanouts shall be Boston Regulation pattern brass cleanouts installed at all points necessary to make all portions of the drainage system accessible for cleaning purposes.

(k) Plumbing Fixtures - Complete with trim, of the latest models of Crane Co., Kohler Co., or Eljer Co., wall hung whenever possible. Drinking fountains to be wall hung electric water coolers.



OUTLINE SPECIFICATIONS - SECTION II - FINISHING (continued)

(1) Fire Extinguishers - Chemical first aid extinguisher designed and built to NEFU requirements. Soda and ash type generally and CO₂ type in mechanical equipment spaces.

(m) Toilet accessories - Mirrors, soap dispensers, shelves, paper dispensers, etc., as required.

(n) Floor and roof drains - Cast iron throughout, with brass strainers as required, Josam, Zurn, Smith, or equal. Wetbasin (15) wall hydrants - non-freeze type - cast bronze.

SECTION III

SECTION III

HEATING AND VENTILATION

III-1. SCOPE. -

The scope of the work, without limit of quantity, shall consist of furnishing and installing complete heating and ventilating systems in the building:-

(a) General. - Each system of heating and ventilating shall be designed to yield flexibility for future expansion.

(b) Heating and ventilating systems. - Heating and ventilating systems included in this Section of the specifications shall be designed to suit tenant requirements.

(c) Boilers. - An automatic steam boiler shall be complete with all appurtenances including piping and valves and shall be rated per hour of steam in the boiler room at 150 lbs. per sq. in. pressure.

(d) Commercial steam. - Commercial steam shall be obtained from a commercial source, at the option of the owner, and shall be delivered at 15 psig with all required piping shall be provided in the manufacturing area instead of the steam generators.

(e) Steam distribution. - Steam and vent pipes shall be in the shafts of the manufacturing areas and office areas including the vertical runs from the boiler room to the shafts and complete with hangers, valves, anchors, and expansion loops or joints.

(f) Capped branch tees. - At each floor, capped branch tees shall be provided on the supply and return lines in the shafts of the manufacturing areas for future connection of piping serving each tenant's manufacturing area.



OUTLINE SPECIFICATIONS - SECTION III - HEATING AND VENTILATION (continued)

(g) Metered steam. - If steam for heating a boiler process is to be metered for each tenant, a condensate meter shall be provided at each tenanted manufacturing area.

(h) Office area heating. - Finned tube baseboard radiation with piping, traps, valves and all accessories for heating the office space to 72°F. when outside temperature is 0°F.

(i) Ventilation. - Ventilation supply and exhaust ductwork in each shaft. Ductwork shall be designed to provide 1.5 CFM per square foot of area.

(j) Toilet Ventilation. - Complete exhaust ventilation systems with roof fans, ductwork and registers to provide 12 air changes per hour.

(k) Insulation. - Pipe insulation as applicable for the service including valves, flanges, fittings and equipment.

III-2. MATERIALS. -

(a) Piping and Fittings. - Steam piping shall be Schedule 40 black steel with malleable iron screwed fittings for piping 2 inches and smaller and welding fittings for piping 2-1/2 inches and larger. Condensate return piping shall be standard weight wrought iron with malleable iron screwed fittings for pipe 2 inches and smaller and wrought iron welded fittings for pipe 2-1/2 inches and larger.

(b) Valves - Gate and Globe. - Low pressure steam valves 2 inches and smaller shall be 125 pound class, bronze, with non-rising stem, screwed ends for sizes up to 2 inches and 125 pounds, flanged ends, cast iron body, bronze trim, outside screw and yoke type for sizes 2-1/2 inches and larger.

(c) High pressure steam valves shall be same as for low pressure except they shall be 250 pound cast iron class.

OUTLINE SPECIFICATIONS - SECTION III - HEATING AND VENTILATING (continued)

(d) Check valves shall be horizontal swing type of materials specified in III-2 (a) and (b).

(e) Pressure Reducing Valves. - Shall be pilot operated 125 or 250 pound cast iron body with stainless steel trim as required for the service. Basket type strainers shall be provided in the inlet connection to each valve. Relief valves shall be provided in the down stream connection with discharge pipe to atmosphere.

(f) Traps. -

(1) Inverted bucket type for dripping high pressure steam lines and equipment.

(2) Float and thermostatic type for low pressure steam lines and equipment.

(3) Thermostatic type for indirect connection of finned tube radiation.

(4) "Y" type strainer at inlet of each steam trap.

(g) Pressure gauges shall be Bourdon tube type and shall be provided at inlet and outlet of pressure reducing valves.

(h) Ductwork shall be galvanized steel of gauges in accordance with the latest edition of the "ASHRAE" Guide.

(i) Registers and grilles shall be of standard manufacturer of the sizes and capacities required.

(j) Fans shall be centrifugal roof type exhausters of size and capacity required, tested and rated in accordance with the AMCA and ASHRAE Codes. Fans shall be equipped with vibration eliminator bases and disconnect switch.



OUTLINE SPECIFICATIONS - SECTION III - HEATING AND VENTILATING (continued)

(k) Flexible Connections. - Asbestos cloth collars shall be provided at the duct connection of each fan.


(l) Fire Dampers. - Metal clad asbestos fire dampers with fusible link shall be provided as required by the Commonwealth of Massachusetts.

(m) Radiation. - Radiation in the office areas shall be finned tube baseboard type complete with shut-off valves and traps.

III-3. TESTING. -

All piping shall be satisfactorily hydrostatically tested prior to installation of insulation. Performance tests shall be conducted for the boiler room equipment, offices, heating systems and toilets exhaust ventilation systems prior to final acceptance.

III-4. MANUFACTURING AREAS VENTILATION SYSTEM shall consist of air handlers with ductwork distribution systems to all processes within each manufacturing area. Air handlers shall take air from the supply duct rail in the building shaft and heating coils in the units shall temper the air as required in cold weather.



OUTLINE SPECIFICATIONS

SECTION IV

ELECTRIC WORK

IV-1. GENERAL. -

(a) All electrical work shall be in accordance with the latest rules and regulations of the National Electrical Code, the Electrical Inspection Department of the City of Boston, the Boston Edison Company, and the Massachusetts Department of Public Safety.

(b) The building owner will provide electric facilities for all secondary service equipment and feeders for all basement lighting and power, for corridor, stairway and foyer lighting, for elevators, street lighting, emergency lighting, and for tenant tenant lighting and convenience outlets.

(c) The respective tenant will provide electric facilities for lighting over and above the basic lighting facilities provided by the building owner and for their individual power requirements including air conditioning.

(d) The building owner will provide electric energy for all basement lighting and power, corridor stairway and foyer lighting, elevators and street lighting. This energy will be metered by a single meter in the basement electric room.

(e) The respective tenant will provide electric energy for all lighting and power consumed within the respective tenant area. This energy will be metered by meters in the electric room adjacent to the tenant area.

IV-2. SERVICE. -

(a) Electric service for the project will be from underground lines of the Boston Edison Company, at either 4160 or 13,800 volts, 3 phase, depending on the building load, with transformation in each building to 120/208 volt, 3 phase, 4 wire.



OUTLINE SPECIFICATIONS - SECTION IV - ELECTRIC WORK (continued)

(b) The Boston Edison Company will furnish and install the underground electric service to the building, charging the building owner for that portion of the installation from a point two feet inside the property line to the building. The Boston Edison Company will furnish and install required transformation and primary disconnects in a transformer vault provided by the building owner within the basement of the building.

(c) The Boston Edison Company will meter the electrical energy required by the building owner at a location in the electric room provided in the basement of the building. The Boston Edison Company will meter the electrical energy required by the respective tenants at the respective electric rooms adjacent to the tenant areas.

IV-3. SERVICE EQUIPMENT. -

(a) In the electric room, in the building basement, adjacent to the transformer vault, there will be a main building service disconnect switch, a building owner's service disconnect switch, facilities for building owner metering, a building owner's panelboard and service disconnect switches controlling the tenant feeders to the electric rooms on the various tenant floors.

(b) In the electric rooms on the various tenant floors, there will be tenant service disconnect switches, facilities for tenant metering and as required building owner panelboards.

(c) Service disconnect switches in the basement electric room will be of the standard type, of adequate size and interrupting capacity for the loads to be served.

(d) Tenant service disconnect switches will be suitable for attachment to bus duct and will be of adequate size and interrupting capacity for the loads to be served.

OUTLINE SPECIFICATIONS - SECTION IV - ELECTRICAL WORK (continued)

(e) Metering facilities will be as required by the loads being served.

IV-4. FEEDERS. -

(a) Feeders supplying building owner panelboards on the tenant floors, used for corridor, stairway and foyer lighting, and feeders to the elevator machine rooms will be of conduit and cable of adequate sizes for the loads being served. These feeders will originate at the building owner's panelboard in the basement electric room.

(b) Tenant feeders to the electric rooms on the various tenant floors will be of plug-in bus-duct type of adequate capacity for the loads being served. These feeders will originate at service disconnect switches in the basement electric room.

(c) In each building, there will be one building owner's panelboard feeder, one feeder for each grouping of elevators and two tenant feeders, one for each tier of electric rooms.

IV-5. PANELBOARDS. -

(a) All panelboards will be of the bolt-in circuit breaker type with the number of branches of sizes and number of poles as required by the loads being served. All panelboards will have lugs only in the mains and will have 3 pole and solid neutral mains.

(b) Building owner panelboards will be located in the various electric closets as required.

(c) Tenant panelboards will be located in the tenant manufacturing areas.

OUTLINE SPECIFICATIONS - SECTION IV - ELECTRIC WORK (continued)

IV-6. RECEPTACLES. -

(a) Convenience receptacles will be located throughout the tenants office and manufacturing areas. Convenience receptacles shall be rated 15 ampere, 125 volt, single phase, grounded type, of specification grade.

(b) Power receptacles in tenant manufacturing areas will be the responsibility of the tenant.

IV-7. WALL SWITCHES. -

(a) Wall switches for control of room lighting will be 20 ampere, totally enclosed, specification grade, single, double, or 3-way as required. Switches shall be A. C. rated.

IV-8. MOTORS. -

(a) All motors shall be of adequate rating for the size and type of loads being served.

(b) Motors rated 1/2 horsepower and lower shall be suitable for operation on 120 volt, single phase.

(c) Motors rated 3/4 horsepower and larger shall be suitable for operation of 208 volts, three phase.

IV-9. FIXTURES. -

(a) Electric fixtures in the office and manufacturing areas will be of the fluorescent type and shall employ the Gibson "Uni-Race" method of installation or an approved equal system. This system employs a basic "Uni-Race" assembly into which the fluorescent fixture units are installed with the electrical connection between the "Uni-Race" assembly and the fixture being made through a plug-in arrangement.



OUTLINE SPECIFICATIONS - SECTION IV - ELECTRIC WORK (continued)

Illumination levels may be increased or decreased by adding or removing fixture units without disturbing the basic "Uni-Race" assembly.

(b) Electric fixtures in the office area will be of the recessed commercial type with option of louver or lens diffusers.

(c) Electric fixtures in the manufacturing area will be of the pendant industrial type.

(d) Only sufficient fixtures to produce an illumination level of twenty foot candles will be installed under this basic contract. Additional fixtures required for higher levels of illumination will be the responsibility of the tenant.

(e) In the office area, there will be two rows of recessed fixtures. In the manufacturing area, there will be three rows of fixtures per bay.

(f) Electric fixtures for the corridors and foyer will be of the recessed fluorescent type, individual units, spaced to give an illumination level of 10 foot candles.

(g) Stairway and toilet room electrical fixtures shall be of the recessed incandescent type of wattage sufficient to produce an illumination level of 10 foot candles.

(h) Electric fixtures for the basement areas will be of the incandescent type with RIM dome reflectors of adequate wattage to produce an illumination level sufficient for the type area being served.

(i) Platform lighting will be of the incandescent type with dome reflectors.



OUTLINE SPECIFICATIONS - SECTION IV - ELECTRIC WORK (continued)

IV-10. WIRING. -

(a) Cables for the underground primary service will be of a size and type as recommended by the Boston Edison Company and will be installed in fiber duct encased in concrete.

(b) Feeder cables, exclusive of the bus-duct feeders, will be of adequate size for the loads being served, will be type RHM, and will be installed in rigid conduit.

(c) Branch circuit wiring will be installed in rigid conduit and electrical metallic tubing. Cables will be type WM.

(d) Street lighting cables will be 2c/c, 600 volt, type RR installed in type II fiber duct, underground.

IV-11. BUS-DUCT. -


(a) Bus-duct for the tenant feeders will be of a size adequate for the loads being served, will be of either copper or aluminum bus, at the option of the Contractor, and will be of the plug-in type. Bus-duct will be installed with all required bends, terminals, fittings or other accessories.

(b) Switches used for the connection of panelboard circuits to the bus-duct at tenant electric rooms, will be of adequate size for the loads being served and will be of a type which will readily plug into the bus-duct.

IV-12. STREET AND AREA LIGHTING. -

(a) Street and area lighting will be of the mercury lamp type of illumination.

(b) Lighting standards will be aluminum poles equipped with a six foot single bracket, transformer base, will allow a mounting height for the luminaire of 27 feet 8 inches, and will be similar and equal to General Electric design No. 277TLb.



OUTLINE SPECIFICATIONS - SECTION IV - ELECTRIC WORK (continued)

(c) Luminaire will produce an IES Type III distribution, will be suitable for use with an H400-E1, mogul multiple socket lamp, and will be similar and equal to General Electric Form 409.

(d) Lamp ballast will be suitable for use with an H400-E1 mercury lamp, will operate on a 208 volt, single phase circuit, and will be located in the transformer base of the lighting standard.

(e) Street and area lighting circuits will be controlled by an astronomical time clock located in the basement electric room.

IV-13. EMERGENCY LIGHTING. -

(a) Emergency lighting units will be located in the corridors and stairways to provide emergency lighting for these areas.

(b) Units will be of the individual 6 volt, nickel-cadmium battery type, with double heads mounted on each unit.

(c) Units will be mounted on wall brackets, located approximately seven feet above floor and will be permanently connected with flexible conduit to wall outlet.

IV-14. TELEPHONE. -

(a) Empty conduits with surface mounted cabinets in the electric rooms, will be installed for the future installation of telephone cable and equipment by the telephone company.

(b) A main terminal cabinet will be located in the basement electric room with one-two inch conduit from this cabinet to the terminal cabinets in each tier of tenant electric rooms.



OUTLINE SPECIFICATIONS - SECTION IV - ELECTRIC WORK (continued)

(c) Main terminal cabinet will be 36" x 24" x 6". Terminal cabinets in the tenant electric rooms will be 18" x 12" x 6". All cabinets will be provided with 1/2" plywood backboards.

(d) Empty 1" conduits will be installed from the terminal cabinet in the tenant electric rooms to telephone outlets in the tenant quarters.

2000

PRELIMINARY ENGINEERING COST ESTIMATE

for a
MULTI-STORY PROTOTYPE LIGHT MANUFACTURING PLANT
in the
SOUTH END URBAN RENOVATION AREA
in the
CITY OF BOSTON

Prepared for
BOSTON REDEVELOPMENT AUTHORITY
BOSTON, MASSACHUSETTS

o o o o o o o o o

W. CHESTER BROWN AND ASSOCIATES, INC.
ARCHITECTS AND ENGINEERS
122-128 Arlington Street
Boston, Massachusetts

CONSULTING ENGINEERS INCORPORATED
122-128 Arlington Street
Boston, Massachusetts

REPORT NO. 4

September, 1963

Project No. 73962

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73962 - B.R.A. FEASIBILITY STUDY -
REPORT NO. 4

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>REPARATION OF SITE - EARTHWORK AND CLEANUP</u>				
Excavation	C.Y.	24,025	\$.60	\$ 14,415.00
Remove Surplus Material	C.Y.	10,000	.80	8,000.00
Building Gravel	C.Y.	500	1.80	900.00
Compacted Gravel	C.Y.	10,500	2.10	22,050.00
sidewalk Gravel	C.Y.	540	2.10	1,134.00
Illuminous Parking Area	S.Y.	12,380	1.60	19,808.00
Illuminous Roads	S.Y.	6,500	2.10	13,650.00
Illuminous Loading Platform Ramp	S.Y.	5,000	2.10	10,500.00
Soam	C.Y.	275	3.00	825.00
Grade, Fertilize and Seed	S.Y.	4,150	.70	2,905.00
Interior Storm Drain	L.S.			45,240.00
Interior Water	L.S.			10,620.00
Interior Sanitary	L.S.			5,700.00
Interior Gas Piping	L.S.			4,740.00
Concrete Walks	S.F.	37,350	.30	11,205.00
Paint Parking Lines	L.S.			300.00
TOTAL (For 5 Buildings)				\$ 171,992.00
$\frac{172,000}{5} = \$34,400.00$				
TOTAL For 1 Building				\$ 34,400.00
Say				\$ 35,000.00

ELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73962 - PRELIMINARY STUDY, B.R.A. -

REPORT NO. 4 (continued)

Description	Unit	Quantity	Unit Cost	Eng. Cost Est.
<u>1ST FLOOR SLAB (1/2 of 1 FLOOR)</u>				
Columns	C.Y.	37	\$ 55.00	\$ 2,000.00
Beams	C.Y.	66	70.00	4,600.00
1st Flat Slab	C.Y.	326	65.00	21,300.00
Face Brick	EA.	17,000	.20	3,400.00
Concrete Blocks	EA.	8,700	.90	7,800.00
Concrete Blocks	EA.	3,000	.70	2,100.00
Partition Wall	S.F.	1,200	5.00	6,000.00
Glazing	S.F.	800	3.00	2,400.00
Glass	S.F.	1,250	1.20	1,500.00
Stairs, Risers	EA.	40	45.00	1,800.00
Stairs, Landing	S.F.	60	6.00	400.00
Plaster Ceilings	S.Y.	90	9.00	800.00
Acoustic Tile Ceilings	S.F.	3,600	.30	2,900.00
Ceramic Tile Walls	S.F.	1,300	1.70	2,200.00
Ceramic Tile Floors	S.F.	780	1.40	1,100.00
Single Doors & Frames	EA.	24	125.00	3,000.00
Overhead Doors	EA.	3	800.00	2,400.00
Boilet Partitions	EA.	10	120.00	1,200.00
Asphalt Tile Flooring	S.F.	3,600	.70	2,500.00
Painting	L.S.			4,000.00
Hardware	L.S.			3,000.00
				<hr/>
				\$ 76,400.00
			Call	\$ 76,500.00

76,500 x 2 = 153,000 per floor

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73362 - E.R.L. PRELIMINARY STUDY -

PORT NO. 4 (continued)

Description	Unit	Quantity	Unit Cost	Eng. Cost Est.
<u>CEMENT</u>				
<u>CONCRETE:-</u>				
Foundation Walls	C.Y.	350	\$ 50.00	\$ 17,500.00
Basement Floor	C.Y.	175	50.00	8,800.00
Columns & Piers	C.Y.	23	60.00	1,100.00
8" Concrete Block	EA.	4,300	.90	4,300.00
Stairs, Risers	EA.	36	45.00	1,600.00
Stairs, Landings	S.F.	64	6.00	400.00
Stairs to Boiler Room	L.S.			400.00
Single Doors & Frames	EA.	6	125.00	700.00
Double Doors & Frames	EA.	4	175.00	700.00
Painting	L.S.			1,000.00
Hardware	L.S.			900.00
				<u>37,400.00</u>

ELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73962 -- R.R. -- PRELIMINARY STUDY --

REPORT NO. 4 (continued)

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>OF - GRID FLAT SLAB</u>				
of Slab	C.Y.	430	72.55.00	\$ 31,200.00
ams	C.Y.	109	70.00	7,600.00
copy Roof Slab	C.Y.	45	60.00	2,700.00
ading Platform	C.Y.	50	50.00	2,500.00
of Insulation	S.F.	25,600	.30	7,700.00
& G Roofing	SQ.	169	32.00	8,600.00
pper Gravel Stop	L.F.	1,324	1.50	2,000.00
enthouses	L.S.			19,000.00
scellaneous Flashing	L.S.			500.00
				<u>\$ 81,800.00</u>
<u>MISCELLANEOUS ITEMS</u>				
Entrance Doors	PR.	4	700.00	\$ 2,800.00
imestone	S.F.	1,260	5.50	8,000.00
obby Stairs	RISEN	6	90.00	500.00
obby	L.S.			2,000.00
obby Railing	L.S.			200.00
				<u>\$ 13,500.00</u>

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT 173912 - D.S. PRELIMINARY STUDY -
REPORT NO. 4 (continued)

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>PLUMBING - 4 STORY BUILDING</u>				
Roof Drainage	L.S.			\$ 4,300.00
Gas Piping	L.S.			2,300.00
Cold Water Piping	L.S.			11,800.00
Hot Water Piping	L.S.			7,000.00
Hot Water Return Piping	L.S.			1,700.00
Sanitary	L.S.			17,000.00
Fixtures	L.S.			30,000.00
Equipment	L.S.			6,700.00
Accessories	L.S.			<u>5,000.00</u>
				\$ 85,800.00
	10% Profit			<u>8,580.00</u>
				\$ 94,380.00
	10% Overhead			<u>9,438.00</u>
	TOTAL PLUMBING COST			\$103,820.00
			Day	\$104,000.00
	Sprinkler Cost			\$ 9,000.00

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73962 - P.D.C. PRELIMINARY STUDY,
REPORT NO. 4 (continued)

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>PLUMBING - 6 STORY BUILDING</u>				
Roof Drainage	L.S.			\$ 4,800.00
Gas Piping	L.S.			2,900.00
Cold Water Piping	L.S.			15,200.00
Hot Water Piping	L.S.			9,500.00
Hot Water Return Piping	L.S.			2,100.00
Sanitary & Vent	L.S.			22,000.00
Fixtures	L.S.			44,000.00
Equipment	L.S.			11,200.00
Accessories	L.S.			<u>7,500.00</u>
				\$ 119,200.00
		10% Profit		<u>11,920.00</u>
				\$ 131,120.00
		10% Overhead		<u>13,120.00</u>
				\$ 144,240.00
		TOTAL PLUMBING COST		\$ 144,240.00
			Say	\$ 145,000.00
		Sprinkler Cost		\$ 40,000.00

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73962 - D.R.I. PL. REPAIRITY STUDY -

REPORT NO. 4 (continued)

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>FIRE PROTECTION AND SPRINKLERS</u>				
<u>STORY BUILDING:-</u>				
Sprinklers - Basement Only				
Area = 6500 s.f.		= 65 Heads		
100 s.f. per head				
65 Heads				
\$30. per head				
1,950 - Say \$3,000 incl. hydrants				\$ 3,000.00
-1/2" First aid standpipe with hose cabs & fire extinguishers				
say 4 units per floor and 2 in basement =				
Total = 18 @ \$200.00 = \$3,600.00				
Piping		2,000.00		
		\$5,600.00		\$ 5,600.00
				\$ 8,600.00
			say	\$ 9,000.00
<u>6 STORY BUILDING:-</u>				
Area = 161,600 s.f.		= 1,616 Heads		
100 s.f. per head				
1,616 Heads @ \$25.00 per head =			say	\$ 40,000.00

REPORT NO. 4 (continued)

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>HEATING AND VENTILATING - 4 STORY BUILDING</u>				
<u>BUILDING HEATING SYSTEM</u>				
INCLUDES:				
Supply & Return Steam Risers for Office Areas - L.S.			\$	300.00
Supply & Exhaust Duct Risers for Office Areas - L.S.				3,300.00
Supply & Return Steam Risers for Manufacturing Areas - L.S.				2,500.00
Supply & Return Duct Risers for Manufacturing Areas - L.S.				7,000.00
Condensate Meters & Basement Piping - L.S.				8,300.00
Exhaust Ducts for Toilets - L.S.				3,300.00
Unit Heaters & Piping for Heating of Non-Conditioning Areas - L.S.				22,300.00
Finned Radiation along the Perimeter of Office Areas - L.S.				20,000.00
Boiler Room Equipment & Piping & Oil Storage System - L.S.				20,000.00
				<u>\$ 87,000.00</u>
<u>MANUFACTURING AREAS VENTILATION</u>				
INCLUDES:				
Air Handling Units, Ductwork and Diffusers - L.S.			\$	29,000.00
TOTAL FOR BUILDING				<u>\$116,000.00</u>

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #72962 - D.R. - PRELIMINARY STUDY -

PORT NO. 4 (continued)

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>HEATING AND VENTILATING -- 6 STORY BUILDING</u>				
<u>BUILDING HEATING SYSTEM</u>				
INCLUDES:				
Supply & Return Steam Risers for Office Areas -	L.S.		\$	500.00
Supply & Exhaust Duct Risers for Office Areas -	L.S.			4,900.00
Supply & Return Steam Risers for Manufacturing Areas -	L.S.			4,900.00
Supply & Return Duct Risers for Manufacturing Areas -	L.S.			9,500.00
Condensate Meters & Basement Piping -	L.S.			9,800.00
Exhaust Ducts for Toilets -	L.S.			4,300.00
Unit Heaters & Piping for Heating of Manufacturing Areas -	L.S.			33,000.00
Finned Radiation along the Perimeter of Office Areas -	L.S.			29,000.00
Boiler Room Equipment & Piping & Oil Storage System -	L.S.			<u>37,100.00</u>
			\$	123,000.00

MANUFACTURING AREAS VENTILATION

INCLUDES:				
Air Handling Units, Ductwork & Diffusers -	L.S.		\$	<u>46,000.00</u>
TOTAL FOR BUILDING			\$	169,000.00

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73062 - E.R.A. FEASIBILITY STUDY -
 REPORT NO. 4 (continued)

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>ELECTRIC WORK - 4 STORY BUILDING</u>				
Electric Room	L.S.			\$ 7,706.00
Boiler Room Feeder, etc.	L.S.			749.00
Basement Panel & Feeder	L.S.			267.00
Owner's feeder tenant floors	L.S.			530.00
Owner's Lighting - Corridors, Stairs, Basement	L.S.			7,010.00
Elevators	L.S.			4,116.00
Tenant Feeders	L.S.			19,234.00
Tenant Area Lighting by Owner (to 22 ft. candles)	L.S.			<u>44,928.00</u>
				\$ 84,590.00
			Say	\$ 85,000.00
<u>ELECTRIC WORK - 6 STORY BUILDING</u>				
Electric Room	L.S.			\$ 3,490.00
Boiler Room Feeder, etc.	L.S.			749.00
Basement Panel & Feeder	L.S.			267.00
Owner's Feeder - Tenant Floors	L.S.			785.00
Owner's Lighting-Corridors, Stairs, Basement - L.S.				9,493.00
Elevators	L.S.			4,469.00
Tenant Feeders	L.S.			28,687.00
Tenant Area Lighting by Owner (to 22 ft. candles) - L.S.				<u>67,392.00</u>
				\$ 120,332.00
			Say	\$ 120,000.00

Based on Gibson fixtures, 2 tube and unit-trace plus office air conditioning.

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73962 - B.R. - PRELIMINARY STUDY -

REPORT NO. 4 (continued)

Description	Unit	Quantity	Unit Cost	Eng. Cost Est.
<u>COST SUMMARY - 4 STORY BUILDING - GRID FLAT SLAB</u>				
Basement				\$ 37,400.00
4 Floors @ \$153,000.00				612,000.00
Ref, etc.				81,800.00
Miscellaneous Items				13,500.00
movable Partitions				42,400.00
Elevators:-				
4 Freight - \$120,000.00				
2 Pass. - 60,000.00				
			\$180,000.00	180,000.00
File Foundations				146,400.00
Site Work				35,000.00
Plumbing				104,000.00
Fire Protection & Sprinklers				9,000.00
Electric				85,000.00
Heating & Ventilating				<u>116,000.00</u>
			TOTAL COST OF BLDG.	\$1,472,500.00
			Call	\$1,473,000.00

AREA OF BUILDING:-

25,700 s.f. per floor

4 floors

1,800

1,500 (Basement)

1,900 Loading Platform

1,200 s.f. total.

$$\frac{\$1,473,000.00}{110,200} = \$13.36 \text{ per s. f.}$$

ELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73961 - B.S.I. FMS-BUILD STUDY -

REPORT NO. 4 (continued)

Description	Unit	Quantity	Unit Cost	Eng. Cost Est.
<u>COST SUMMARY - 6 STORY BUILDING - GRID PLAT SLAB</u>				
Basement				\$ 37,400.00
Floors @ \$153,000.00				918,000.00
Roof, etc.				81,800.00
Miscellaneous Items				13,500.00
movable Partitions				63,600.00
Elevators:				
4 Freight - \$140,000.00				
2 Pass. - <u>72,000.00</u>				
				<u>\$212,000.00</u>
				212,000.00
Foundation				195,200.00
Site Work				35,000.00
Plumbing				145,000.00
Fire Protection & Sprinklers				40,000.00
Electric				120,000.00
Heating & Ventilating				<u>169,000.00</u>
			TOTAL COST OF BUILDING	\$2,030,500.00
			Call	\$2,031,000.00

AREA OF BUILDING:-

4 Story Building 110,200 s.f.
 Add for 2 floors
 2 x 25,700 s.f. = 51,400
 161,600 s.f.

$$\frac{\$2,031,000.00}{161,600 \text{ s.f.}} = \$12.56 \text{ per s.f.}$$

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73962 - D.P. - FEASIBILITY STUDY -

REPORT NO. 4 (continued)

<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Eng. Cost Est.</u>
<u>COST SUMMARY - 4 STORY BUILDING - FLAT SLAB WITH DROP PANELS</u>				
Basement				\$ 37,400.00
4 Floors @ \$156,500.00				626,000.00
Roof, etc.				82,840.00
Miscellaneous Items				13,500.00
movable Partitions				42,400.00
Elevators				180,000.00
File Foundations				157,600.00
Site Work				35,000.00
Painting				104,000.00
Fire Protection & Sprinklers				9,000.00
Electric				25,000.00
Heating				116,000.00
				<hr/>
			TOTAL COST OF BUILDING	\$1,488,740.00
			Call	\$1,489,000.00

$$\frac{\$1,489,000.00}{110,200 \text{ s.f.}} = \$13.51 \text{ per s.f.}$$

PRELIMINARY ENGINEERING COST ESTIMATE, PROJECT #73962 - P.B.A. INVESTIGATIVE STUDY -

PORT NO. 4 (continued)

Description	Unit	Quantity	Unit Cost	Eng. Cost Est.
T SUMMARY - 6 STORY BUILDING - FLAT SLAB WITH DROP PANELS				
Cement				\$ 37,400.00
Floors @ \$156,500.00				939,000.00
Plaster, etc.				82,840.00
Miscellaneous Items				13,500.00
Wall Partitions				63,600.00
Elevators				212,000.00
Foundations				208,000.00
Paint Work				35,000.00
Piping				145,000.00
Fire Protection & Sprinklers				40,000.00
Electric				120,000.00
Finishing				169,000.00
TOTAL COST OF BUILDING				\$ 2,065,340.00
			Call	\$ 2,066,000.00
$\frac{\$2,066,000.00}{161,600 \text{ s.f.}} = \12.78 per s.f.				

COMPUTATIONS

PRELIMINARY ENGINEER'S COST
SUBJECT: ESTIMATE, B.I.A. FACILITY STUDY

PREP. BY

SHEET 15

COST ANALYSIS, SHOWING PLACEMENT OF
TOTAL BUILDING COST AT VARIOUS STAGES TO
ELEVATORS, PILE FOUNDATIONS, SITE WORK,
PLUMBING, FIRE PROTECTION & SPRINKLERS,
ELECTRIC, HEATING.

CHKD.

APPRD.

PROJ. 17-15-

REPORT #4

DATE SEP 19, 1963

BE USED ONLY WITH ACCOMPANYING DATA

		1 STORY FLAT SLAB	1 STORY GRID FLAT SLAB	2 STORY FLAT SLAB	2 STORY GRID FLAT SLAB
TOTAL COST		\$ 489,000	\$ 1,473,000	\$ 2,066,000	\$ 2,031,000
COST PER SQ. FT.		\$ 13.51	\$ 13.36	\$ 12.78	\$ 12.56
ELEVATORS	COST	\$ 85,000	\$ 125,000	\$ 210,000	\$ 210,000
	% OF TOTAL COST	17.4%	8.5%	10.2%	10.4%
	COST PER SQ. FT.	\$ 1.13	\$ 1.69	\$ 1.31	\$ 1.31
PILE	COST	\$ 157,000	\$ 146,400	\$ 232,000	\$ 195,000
EVALUATION	% OF TOTAL COST	32.1%	9.9%	11.2%	9.6%
	COST PER SQ. FT.	\$ 1.43	\$ 1.33	\$ 1.29	\$ 1.21
CONCRETE	COST	\$ 35,000	\$ 35,000	\$ 35,000	\$ 35,000
	% OF TOTAL COST	7.2%	2.4%	1.7%	1.7%
	COST PER SQ. FT.	\$.32	\$.32	\$.32	\$.32
PLUMBING	COST	\$ 104,000	\$ 104,000	\$ 145,000	\$ 145,000
	% OF TOTAL COST	21.3%	7.1%	7.0%	7.1%
	COST PER SQ. FT.	\$.94	\$.74	\$.70	\$.70
FIRE	COST	\$ 200,000	\$ 200,000	\$ 400,000	\$ 400,000
PROTECTION	% OF TOTAL COST	41.0%	13.6%	19.4%	19.7%
& SPRINKLERS	COST PER SQ. FT.	\$.60	\$.60	\$.65	\$.65
ELECTRIC	COST	\$ 80,000	\$ 125,000	\$ 120,000	\$ 120,000
	% OF TOTAL COST	16.4%	8.5%	5.8%	5.9%
	COST PER SQ. FT.	\$.77	\$.75	\$.55	\$.55
HEATING	COST	\$ 110,000	\$ 110,000	\$ 160,000	\$ 160,000
	% OF TOTAL COST	22.5%	7.5%	7.8%	7.9%
	COST PER SQ. FT.	\$.85	\$.75	\$.75	\$.75

COMPUTATIONS

Architects and Engineers

2-128 ARLINGTON STREET
BOSTON 16, MASS.

HUBBARD 2-6060

SUBJECT

E. E. H.

PREP. BY

SHEET

1016

CHKD.

PROJ.

73900

APPRD.

DATE

SEPT. 11

BE USED ONLY WITH ACCOMPANYING DATA

MS

TYPICAL R&D - VOLUME OF CONCRETE

$$25' \times 28' = 700 \text{ sq. ft.}$$

EX. DOME 2 PLACES 1175' ²/₂

$$\text{SLAB } 700 \times 100 = 800 \text{ C.F.}$$

$$171 \text{ DUMPS CUT } \times 1.75 = 300$$

$$\frac{550}{27} = 20.5 \text{ C.F.}$$

FOR 1/2 FLOOR

$$20.5 \times 13 \text{ BAYS} = 266 \text{ C.F.}$$

WALLS

FRONT & REAR

$$2 \times 12 \times 12 = 300 \text{ sq. ft.}$$

ALL WALLS

$$7 \times 8' = 56$$

STAIRS

$$2 \times 12 \times 12 = 300 \text{ sq. ft.}$$

$$2 \times 12 \times 12 = 300 \text{ sq. ft.}$$

$$= 171$$

$$20.5 \text{ C.F.}$$

$$\frac{20.5 \text{ C.F.}}{4} = 5.125 \text{ C.F.}$$

$$500 \times 1.0 = 500 \text{ C.F.}$$

$$\text{NET VOL.} = \frac{500 \text{ C.F.}}{1000}$$

COLUMNS

VOL. OF COLUMNS


$$\frac{1.5 \times 14.1 \times 132}{2} = 13.6 \text{ C.F.}$$

1.5 C.F.

$$1.33 \times 14.1 \times 14.1 = 32.0 \text{ C.F.}$$

$$45.6 \text{ C.F.}$$

$$26.5 \text{ C.F.} \times 4.1 = 109.0 \text{ C.F.}$$



SUBJECT Z. L. R.

PREP. BY

SHEET 2 of 16

GRAB FLOOR SLAB

CHKD.

PROJ. 73762
REPORT # 4

TYPICAL FLOOR

APPRD.

DATE SEPT 1963

BE USED ONLY WITH ACCOMPANYING DATA

MS VOLUME OF CONCRETE 1/2 FLOOR CONT'D

BEAMS

SPRINKLER

$$\frac{336 \text{ L.F.} \times .83 \times 3'}{27} = 31 \text{ cu. yd.}$$

AT ELEV. & STAIR OPENING

$$\frac{436 \text{ L.F.} \times .83 \times 2.5}{27} = 35 \text{ cu. yd.}$$

66 cu. yd.

FLOOR 72" x

$$100' \times 12' \times .125 = 150 \text{ cu. yd.}$$

ADD FOR 12" FL.

(AVERAGE TO 4 THICKNESS)

$$100 \times 12' = 1200 \text{ sq. ft.}$$

- MINIMUM

$$17.44 \times 5.5' = -370$$

$$\frac{1200}{4} = 210$$

REAR

$$114' \times 12' = 1368$$

- MINIMUM

$$\frac{420}{4} = 105$$

150

REAR

$$114' \times 12' = 1368$$

- MINIMUM

$$\frac{420}{4} = 105$$

105

$$2324 \times 7\frac{1}{2} = 17430 \text{ cu. yd. (1/2 FLOOR)}$$

8" CONCRETE BLOCK

EXTERIOR WALLS

$$2324 \text{ sq. ft.} = 24' \text{ H.} \times 97 \text{ L.F.} = 2328 \text{ sq. ft.} = 2640 \text{ cu. yd.}$$

PARTITIONS

SET, TANK, & SPACES

$$126 \text{ L.F.}$$

MAIN CORRIDOR

$$224$$

STAIR HALL & STAIRWELL

$$70$$

ELEV.

$$60$$

$$486 \text{ L.F.} \times 11'4" = 5540 \text{ sq. ft.} = 54'6" \times 100' = 5460 \text{ sq. ft.}$$

8580
SAY 8500 BLOCKS

SUBJECT B. Z. A.

PREP. BY hcl.

SHEET 3 of 6

080 FLAT SLAB

CHKD.

PROJ. 751
RENOV. #4

7.7000 FLOOR 1/2

APPRD.

DATE SEPT. 1960

BE USED ONLY WITH ACCOMPANYING DATA

4" CONCRETE BLOCK 1/2 FLOOR

$$200 \text{ L.F.} \times 8'6" \text{ HT} = 1700$$

$$90' \times 11' \text{ HT} = 990$$

$$\frac{1700}{20} = 85 \text{ S.F.} \times 110 = 9350 \text{ BLOCKS}$$

CURTAIN WALL INCLUDES SASH BUT NOT GLAZING

$$\frac{38}{2}$$

$$\frac{84}{2}$$

$$\frac{14}{2}$$

$$\frac{14}{2}$$

$$1' \text{ L.F.} \times 12' \text{ HT} = 12 \text{ S.F.}$$

SASH

ENG WALL

$$10' \text{ L.F.}$$

$$\frac{3}{2} \times 4'$$

$$6.5 \text{ L.F.} \times 3' \text{ HT} = 19.5 \text{ S.F.}$$

REAR WALL

$$11' \text{ L.F.}$$

$$\frac{4}{2}$$

$$7.5 \text{ L.F.} \times 5.5' \text{ HT} = 41.25 \text{ S.F.}$$

GLAZING

FRONT WALL

$$21' \text{ L.F.}$$

$$\frac{4}{2}$$

$$10.5 \text{ L.F.} \times 5.5' \text{ HT} = 57.75 \text{ S.F.}$$

ENG WALL

$$= 352$$

REAR

$$= 41.25$$

$$\frac{1232}{9}$$

MASTER GLAZING (TOTAL AREA ONLY)

$$\frac{45 \times 18 = 810 \text{ S.F.}}{9} = 90 \text{ S.F.}$$

COMPUTATIONS

Architects and Engineers

2-128 ARLINGTON STREET
BOSTON 16, MASS.

HUBBARD 2-6060

SUBJECT 27 L.

PREP. BY 11/1

SHEET 4-16

20" F - 18" W FLAT SLAB

CHKD.

PROJ. 737-2
DEVELOP #4

APPRD.

DATE SEPT 1962

BE USED ONLY WITH ACCOMPANYING DATA

MS

TYPICAL 20" F - 18" W FLAT SLAB
25' x 25' = 625 SF EA. DOME DISPLACES 1.5' C.F.

$$78 \times 1.33' = 103.74 \text{ C.F.}$$

80 DOME DISPL.

$$150 \times 1.5' = 225 \text{ C.F.}$$

$$\frac{410 \text{ C.F.}}{27} = 15 \text{ C.F.}$$

$$32 \text{ DOME} \times 1.5' \text{ C.F.} = 48 \text{ C.F.}$$

SEAM - 2.5' W

$$\frac{192 \text{ C.F.} \times 1.33 \times 3'}{27} = 68 \text{ C.F.}$$

SEAM -

$$\frac{192 \text{ C.F.} \times 1.33 \times 2'}{27} = 48 \text{ C.F.}$$

1.33 C.F. TOTAL

CRACKS - 20" x 20"

$$\frac{192 \text{ C.F.} \times 1.33}{27} = 48 \text{ C.F.}$$

LOADING - 20" x 20"

$$\frac{224 \text{ C.F.} \times 1.33}{27} = 55 \text{ C.F.}$$

ROOF - 18" x 20"


$$114 \times 2.6' = 297 \text{ C.F.}$$

TOTAL - 20" x 20"

$$114 \times 2.6' = 297 \text{ C.F.}$$

$$114 \times 2.6' = 297 \text{ C.F.}$$

$$114 \times 2.6' = 297 \text{ C.F.}$$



14 02 55

Chester Browne
and ASSOCIATES, INC.

COMPUTATIONS

Architects and Engineers
128 ARLINGTON STREET
BOSTON 16, MASS.
HUBBARD 2-6060

SUBJECT

7.7.1.1

PREP. BY

SHEET

601.16

CHRG. TIME RE-FLAT SLAB WITH

CHKD.

PROJ.

Recess #1

DRIP DRAINAGE

APPRD.

DATE

5/27/63

BE USED ONLY WITH ACCOMPANYING DATA

45

TYPICAL BAY - VOLUME OF CONC.

1 SLAB OF 21' X 27' X 5" THICK

DROPPABLE RECESS 3' X 3' X 3" = 32

$$\frac{21 \times 27 \times .83}{27} = 28 \text{ cu. per bay}$$

FOR 2 BAYS

27' X 27' = 368 cu.

5000

FLUOR. 2000

$$\frac{21 \times 27 \times .83}{27} = 28 \text{ cu.}$$

PAID 5000

$$\frac{71 \times 27 \times .83}{27} = 111$$

5000

$$\frac{21 \times 27 \times .83}{27} = 28$$

101 - 4 - 111

NET CONC. = 764.8 cu. per bay

- 152 (FLUOR. RECESS)

- 52.2 (FLUOR. RECESS)

- 111 (FLUOR. RECESS)

5350 - 111 = 5239

4 - 111

5350 - 111 = 5239

5239

5239

Chester Browne
and ASSOCIATES, INC.

Architects and Engineers

128 ARLINGTON STREET
BOSTON 16, MASS.

HUBbard 2-6060

COMPUTATIONS

SUBJECT 20' x 20' SLAB

PREP. BY

SHEET

7 of 16

CONC. TAKEOFF - FLAT SLAB WITH CHKD.

PROJ. 33164
REPORT # 3

GROUP TAKEOFF APPRD.

DATE APR 1962

ROOF SLAB

BE USED ONLY WITH ACCOMPANYING DATA

MS

6" SLAB, 10" AT DEEP TIE-IN

VOL. OF CONC.

S-LAB 20' x 20', 5 = 512 C.Y.

EXTRA CONC. 1.5' x 1.5' x .23 = 24

4.1 C.Y. = 15' C.Y. PER BAY

= 7

22 BAYS

416 C.Y.

- 420 C.Y. PER FLAT AS

16 C.Y. MORE THAN GRID

5 65' PER C.Y.

+ 1340 MORE THAN GRID

BE USED ONLY WITH ACCOMPANYING DATA

15

PAVEMENT FLOOR SLAB

$$\frac{112' \times 56' \times .75'}{27} = 175 \text{ C.Y.}$$

PAVEMENT FL. GREATER WALL

$$\frac{340 \text{ L.F.} \times 1' \times 13.25'}{27} = 167 \text{ C.Y.}$$

12" FOR 200, 200' PERIMETER WALL

$$\frac{120 \text{ L.F.} \times 3'}{27} = 27 \text{ C.Y.}$$

GRADE EXIST. GRAVEL STAGE

$$28' \text{ L.F.} \times 6.5' \text{ DEPTH} = 1840 \text{ SF}$$

$$+ 138 \text{ L.F.} \times 6.5' \text{ DEPTH} = 900 \text{ SF}$$

$$\frac{2740}{27} = 101 \text{ C.Y.}$$

EXIST. PIT WALL

AT 200, 200'

$$30 \text{ L.F.} \times 1' \text{ DEPTH} = 30 \text{ C.F.}$$

FRONT AT 200'

$$76 \text{ L.F.} \times 1' \text{ DEPTH} = 76 \text{ C.F.}$$

FRONT AT END

$$30 \text{ L.F.} \times 1' \text{ DEPTH} = 30 \text{ C.F.}$$

PAV. EL.

$$42 \text{ L.F.} \times 1' \text{ DEPTH} = 42 \text{ C.F.}$$

$$\frac{180 \text{ C.F.}}{27} = 6.7 \text{ C.Y.}$$

EXIST. AT 200' STAGE

$$\frac{134 \text{ L.F.} \times 4' \text{ DEPTH}}{27} = 20 \text{ C.Y.}$$

$$\text{TOTAL} = 348 \text{ C.Y.} \quad \text{CALL } 350 \text{ C.Y.}$$

200' STAGE


$$3 \text{ IN. FILL} \times 20' = 6 \text{ C.Y.}$$

$$16 \text{ EXT. OF WALLS} \times 1' = 16 \text{ C.F.}$$

$$16 \text{ C.F.}$$

8" CONC. FILL

$$428 \text{ L.F.} \times 10' \text{ H.T.} = 4280 \text{ SF} = 43 \text{ SF} \times 10 = 430 \text{ BLOCKS}$$



COMPUTATIONS

Architects and Engineers
128 ARLINGTON STREET
BOSTON 16, MASS.
HUBBARD 2-6060

SUBJECT B. K. L.

PREP. BY 7/

SHEET 9 of 16

PILE FOUNDATIONS

CHKD.

PROJ. 7396
REPORT # 3

G. R. 12 FLAT. SUBS.

APPRD.

DATE SEP. 1963

BE USED ONLY WITH ACCOMPANYING DATA

MS

PILE CAPACITY = 100 TONS PER PILE
AVERAGE LENGTH = 80' + 70' PER L.F. = 2500' PER PILE

ROOF

$$7 \times 12 \times 4 \times 22 \times 70' = 70' \text{ ft}$$

DEAD LOAD =


$$CING = 78' \times 23' \times 150' = 17' \text{ ft}$$

$$- 13 \times 2 \times 55 \times 150' \times 150' = \frac{-21}{61' \text{ ft}}$$

$$70' + 17' = 87' \text{ ft} = \frac{6240}{6724'}$$

$$\text{LIVE LOAD} = 18' \times 30' \times 30' = \frac{16200}{2340'}$$

$$16200' \div 7000' = 2.31 \text{ ft} \text{ (AVERAGE)}$$



7' x 12' FLOOR

7' x 12' FLOOR

DEAD LOAD

$$12' \times 12' \times 100' \times 100' = 120000' \text{ ft}$$


$$- 17' \times 2 \times 55 \times 100' \times 100' = \frac{-18700}{80100'}$$

LIVE LOAD

$$12' \times 12' \times 100' \times 100' = 120000' \text{ ft}$$

$$70' \times 125' = \frac{8750}{150' \text{ ft}}$$

$$150' \div 70' = 2.14 \text{ ft} \text{ (AVERAGE)}$$



LIVE FOR FLOOR TO FLOOR + STAY 8' x 8'

$$8' \times 8' = 64' \text{ ft}$$

$$4 \text{ FLOOR } 118200' = 722' \text{ ft}$$

$$600' \times 125' \times 50' \times 475' = \frac{1781250}{140' \text{ ft}}$$

$$140' \div 100' = 1.4 \text{ ft} \text{ (AVERAGE)}$$

FOR FLOOR 5' x 5'

$$2 \text{ FLOOR } 122' \times 122' = 364' \text{ ft}$$

$$100' \times 125' \times 125' \times 125' = \frac{1562500}{1231600'}$$

$$1231600' \div 1000' = 1231.6' \text{ ft}$$

Chester Browne
and ASSOCIATES, INC.

COMPUTATIONS

Architects and Engineers

128 ARLINGTON STREET
BOSTON 16, MASS.

Hubbard 2-6060

SUBJECT

R & L

PREP. BY

08/1

SHEET 11 OF 16

DATE 8/1/65

CHKD.

PROJ. 7396-
REPORT # 4

8/12/65 EAST SLAB

APPRD.

DATE SEP 15 65

BE USED ONLY WITH ACCOMPANYING DATA

MS

BASEMENT R & L

INTERIOR COL. 4 (4 x 15)

TYPICAL COL. 2'D = 14' 5"

AREA FOR PLATE ONLY

244.5 x 172

244.5 x 128

$240 \frac{1}{2} \times 20 \times 172 = 192$

244.5 x 128

$1628 \times 20 \times 15 = 48840$

$140,000$

$= 52 \times 745$

$= 5 \text{ PILES}$

FOR 6 FLOOR AREA

$244.5 \times 172 = 42054$

CONCRETE

$3 \times 172 = 516 \text{ TONS}$

500

$73 \text{ TONS} = 7 \text{ PILES}$

COL. 2' 4' PILES

TYPICAL COL. 2'D = 14' 5"

AREA FOR PLATE ONLY = 9500

244.5 x 128

42000

$73 \text{ TONS} = 7 \text{ PILES}$

FOR 6 FLOOR AREA


$244.5 \times 172 = 42054$

CONCRETE

$1 \text{ TON} = 5 \text{ PILES}$

COL. 2' 4' PILES = 5 PILES

" " " " = 7 PILES



and ASSOCIATES, INC.

Architects and Engineers

128 ARLINGTON STREET
BOSTON 16, MASS.

HUBbard 2-6060

SUBJECT

PREP. BY

SHEET

CHKD.

PROJ.

APPEND.

DATE _____

BE USED ONLY WITH ACCOMPANYING DATA

ROSEMENT AREA

Col. J. E. ...

1. SURF A - A ECTOPY - - - VULVULUS TAKE PILL FOR 4 DAYS

7 " " 6

2014.12.12

[illegible]

400

1. *Phragmites* (Common Reed)

$$r = 3.2 \times 10^7 \text{ m} \quad \therefore T_{\text{orb}} = 4.3 \text{ hrs}$$

6. ELDER 132

1000

WAC 280.40.010

14 1 1 1 1

25. 4. 7

13 32 0 - 5 = 5:17:45 = 5 p.m.

COMPUTATIONS

Chester Browne

and ASSOCIATES, INC.

Architects and Engineers

128 ARLINGTON STREET
BOSTON 16, MASS.

HUBBARD 2-6060

SUBJECT R. Z. X. PREP. BY 1/26/ SHEET 12 OF 16
FILE # 11-11-11 CHKD. 7/27/ PROJ. 722
FLKT. SLAB WITH DEC. PA. 10.5 REPORT # 1
APPRD. SEPT. 1963 DATE

BE USED ONLY WITH ACCOMPANYING DATA

MS

LOAD PER COL (TYPICAL BAY) 451 K

FOR GRID FEET 10.2 5

422 TONS

DEAD LOAD (FLAT SLAB)

612 C.F. X 150 = 91,800

DEAD LOAD (C.F. SLAB) = 82,000

11,500 FEET FLAT SLAB 10.25 X 10.25

4 TONS

450000 =

22 TONS

$\frac{1145}{105} = 5.19$ PILES

LOAD PER COL (TYPICAL BAY) 65,000

FOR GRID FEET 10.2 5

618 TONS

FOR FEET 10.2 42 11,300 = 10,000

34 "

$\frac{645}{105} = 6.14$ PILES

TYPICAL COL 42 AT 10.2 11.300, AREA 5.000

1. TYPICAL T. 22,000 (4 T. 11.300) =

44 TONS

LIVE LB REDUCTION 1/2 BAY = 2.75

TYPICAL LIVE LB = 2.75

LIVE LB REDUCTION 1/2 BAY = $\frac{8.75}{1.3} \times 3.14 = 2.1$

$\frac{11,000}{645} = 34$ TONS

41 TONS = 4 PILES

T. 10.2 10.25

CO TYPICAL T. 22,000 (4 T. 11.300) =

645 TONS

LIVE LB REDUCTION 1/2 BAY X 10.2 11.300 = $\frac{8.75}{1.3} \times 3.14 = 2.1$

50 "

545 TONS = 6 PILES

SUBJECT B.C.R.

PREP. BY

SHEET

14 of 16

7/1/62

CHKD.

PROJ.

72762

244 1/2 #19

11/1/62

APPRD.

DATE

SEP-1962

BE USED ONLY WITH ACCOMPANYING DATA

MS

11/1/62

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

10 + 1 = 11

SUBJECT B. R. L.

PREP. BY 1/2/71

SHEET 15 OF 16

INCREASED ELEVATORS

CHKD.

PROJ. 7376

REPORT # 1

APPRD.

DATE SEP 11 71

BE USED ONLY WITH ACCOMPANYING DATA

MS

45 PERSONS PER TENANT SPACE

4 TENANT SPACES PER FLOOR

180 PERSONS PER FLOOR

2 FLOORS ABOVE THE GROUND FL. 2

540 PERSONS

DESIRABLE CARRYING CAPACITY = 1200 IN 5 MIN. PER

540 X 1.3 = 70 PERSONS IN 5 MIN.

TRAVEL = 12' X 3 = 36'

USE 2000 LB. CAR CAPACITY

12 PEOPLE " "

SPEED 100 FT. PER MIN.

10 PASSENGERS PER TRIP TO FL.

ROUND TRIP TIME = 90 SECONDS

WAITING INTERVAL FOR 4 ELEVATORS = $\frac{90}{4} = 22.5$ SECONDS

" " " 2 " = $\frac{90}{2} = 45$ SECONDS (OK)

IN 5 MINUTES 1 CAR WILL MAKE $\frac{5 \times 60}{90} = 3.33$ TRIPS

@ 10 PASSENGERS PER TRIP 1 CAR WILL CARRY 33.3 PERSONS IN 5 MIN.

2 CARS WILL CARRY 66.6 PERSONS IN 5 MIN. (THIS IS 14%)


USE 2 ELEVATORS.

FOR 4 STORY BLDG. 2 TRIP ELEVATORS @ \$30,000 - EA. = \$60,000 -

FOR 6 " " " " " @ \$36,000 - EA. = \$72,000 -

(IF JUMP SELECTIVE (CAR ANSWERS CALLS BEHIND THE OTHER)

PUSH BUTTON - NO ATTENDANT.



SUBJECT B.L.L.

PREP. BY 1/1

SHEET 6 E 6

FREIGHT ELEVATORS

CHKD.

PROJ. 7-190

DEPT. #4


APPRD.

DATE SEP 11 52

BE USED ONLY WITH ACCOMPANYING DATA

MS


FOR UP TO 6 STORIES
USE 10' x 10' PLATFORM
5000 LBS. CAPACITY
CLASS "C" LEADING
MANUALLY OPERATED BI-FOLDING DOORS
(VERTICAL SLIDING - 7' H x 2' W),
SINGLE AUTOMATIC CONTROL
SPEED 75 FT. PER MIN.




FOR 4 STORIES 3229, 4 FREIGHT ELEVATORS @ \$35,000 - EA. = 140,000 -

FOR 6 STORIES 3229, 6 FREIGHT ELEVATORS @ \$35,000 - EA. = 210,000 -


SCHEME #1-CONCRETE FLAT SLAB WITH DROP PANELS



SCHEME #2-CONCRETE BEAM AND SLAB




SCHEME #3-CONCRETE JOIST AND BEAM




COST ESTIMATE

SCHEME #1	
REINF.	\$ 0.75 P.S.F.
CONCRETE	\$ 0.40 P.S.F.
FORMS	\$ 0.68 P.S.F.
TOTAL COST PER SQ. FT. \$ 1.83	
SCHEME #2	
REINF.	\$ 0.80 P.S.F.
CONCRETE	\$ 0.79 P.S.F.
FORMS	\$ 1.26 P.S.F.
TOTAL COST PER SQ. FT. \$ 2.85	
SCHEME #3	
REINF.	\$ 0.92 P.S.F.
CONCRETE	\$ 0.74 P.S.F.
FORMS	\$ 0.74 P.S.F.
TOTAL COST PER SQ. FT. \$ 2.43	
SCHEME #4	
REINF.	\$ 0.91 P.S.F.
CONCRETE	\$ 0.56 P.S.F.
FORMS	\$ 0.74 P.S.F.
TOTAL COST PER SQ. FT. \$ 2.21	
SCHEME #5	
STRUCTURAL STEEL	\$ 1.10 P.S.F.
REINF.	\$ 0.16 P.S.F.
CONC.	\$ 0.21 P.S.F.
FORMS	\$ 0.83 P.S.F.
COL. LIN.	\$ 0.19 P.S.F.
TOTAL COST PER SQ. FT. \$ 2.49	
SCHEME #6	
PRESTRESSED TEES	\$ 1.50 P.S.F.
CONC. TOPPING	\$ 0.50 P.S.F.
PRESTRESSING GLANDS	\$ 0.99 P.S.F.
PAINT LAST COLUMN	\$ 0.23 P.S.F.
TOTAL COST PER SQ. FT. \$ 3.22	


SCHEME #4-2 WAY GRID FLAT SLAB



SCHEME #5-CONCRETE SLAB ON FIRE-PROTECTED STEEL BEAMS




SCHEME #6-PRESTRESSED DOUBLE TEES ON PRESTRESSED GLANDS



NOTE: ALL SCHEMES ARE BASED ON A LIVE LOAD OF 150 P.S.F.	
PRELIM. AREA = 903	
PROPOSED PARKING, SURVEYED FOR CIVIL ENGINEERING STUDY	
W. CHESTER BROWNE AND ASSOCIATES ARCHITECTS	
ALBERT GOLDBERG AND ASSOCIATES STRUCTURAL ENGINEERS	
PROJECT	DRAWING
DATE	DATE

CONSTRUCTION	4 STORY BLDG.	6 STORY
FLAT SLAB WITH DROP PANELS	177 PILES 3 @ 800 = \$ 142,500	240 PILES 3 @ 800 = \$ 208,000
GRID FLAT SLAB	193 PILES 3 @ 800 = \$ 142,500	244 PILES 3 @ 800 = \$ 195,200

[illegible]

TYPICAL BUILDING
FOR VOLUNTARY DEVELOPMENT STUDY
SOUTH AND BOSTON

W. C. STERRETT AND ASSOCIATES
ARCHITECTS ENGINEERS
STREET BOSTON, MASS.

75962 | A-11

PROJECT 15 MAY 61

FIN SHED FLOOR LINE

12'-0"

12'-0"

12'-0"

27'-0" ± 3'-0"

12'-0" ± 3'-4"

FINISHED FLOOR LINE

STEEL STUD NAILER
GALVANIZED ANCHORS
PROTECTED COPPER FLASHING
DOVETAIL ANCHOR SLOTS &
GALVANIZED BRICK ANCHORS
BITUMINOUS DAMPPROOFING
CONCRETE INVERTS &
CONTINUOUS SHELF L
PROTECTED COPPER FLASHING
STEEL PROJECTED SASH

STONE SILL
PROTECTED COPPER FLASHING
BRICK

EAVE DETAIL

WINDOW JAMB

CONCRETE COLUMN

CONCRETE BLOCK

TYPICAL WALL SECTION

3/4" = 1'-0"

11 MAY 1965 - SEPT. 1965

TYPICAL BUILDING
FIELD RESEARCH DEVELOPMENT STUDY
SOUTH END
BOSTON

AND ASSOCIATES
ARCHITECTS
BOSTON, MA

73962 4-14
PROJECT SHEET NO. 1
BY DAT



